



Current Projects

NUCA - Engineers Night
February 16, 2010

City of Beaverton, OR

South Central 'C' Westside Interceptor Improvements

Description: Realignment of 1,150 LF of 42" CMP storm sewer, and CIPP lining of 1,900 LF of 30" to 42" CMP pipe. Project includes associated connecting storm improvements totaling 1,400 LF of 12", 15", and 18" storm pipe.

Est. Construction Cost: \$1.5 Million
Est. Construction Date: Summer 2010

South Central 'C' Phase III Utility Improvements (Erickson Interceptor)

Description: Reconstruction of 2,500 LF of 8" sanitary sewer main, 1,000 LF of 18" and 21" sanitary sewer. Approximately 1,600 LF of sewer can be rehabilitated using either open trench or trenchless construction techniques. 1,000 LF of sanitary sewer laterals are to be reconstructed to the 40 homes. Project includes reconstruction of 3,000 LF of 8" water main.

Est. Construction Cost: \$1.4 Million
Est. Construction Date: Spring/Summer 2010

City of Oregon City, OR

Main Street, 5th to 15th Street

Description: Sidewalk reconstruction project along Main Street. Improvements include curb, gutter, sidewalk replacement, and street lighting. Water services, meters, and sanitary laterals will be replaced from the main to the buildings. A new storm sewer will be constructed under a separate contract.

Est. Construction Cost: \$1.9 Million
Est. Bidding Date: Spring 2010

Beavercreek Road/Molalla Ave Intersection Improvements

Description: Construction of a west leg of Beavercreek Road at Molalla Avenue to accommodate a right turn lane. Project includes signal improvements and minor storm, traffic loop, and landscaping improvements.

Est. Construction Cost: \$400,000
Est. Bidding Date: Fall 2010

City of Washougal, WA

'E' Street Improvement Project

Description: This project primarily consists of a road diet from 6th Street to 32nd Street. Improvements include replacement of the existing traffic signal at 'E' and 17th Street, portions of utility upgrades, including water and storm sewers. Additional signal modifications at 'E' and 6th, and 'E' and 32nd streets.

Est. Construction Cost: \$4.5-5.6 Million (11 Bid Alternatives)
Est. Construction Date: May 2010

Skamania County

Cape Horn Trail SR-14 Underpass

Description: Construction of two pedestrian/equestrian tunnels underneath SR-14 near Salmon Falls Road, and Cape Horn Bridge. Tunnel cross section is approximately 10' x 12' totaling 105' long. Project will be a separate schedule added onto Washington Department of Transportation SR-14 realignment project.

Est. Construction Cost: \$2.5 Million (tunnel scope only)
Est. Construction Date: Spring 2010

Tualatin Valley Water District

Bronson Road Water Improvements

Description: Reconstruction of 745 LF of 12-inch water main within Bronson Road at the intersection of NW 174th Avenue. Project is to be constructed before June to accommodate ODOT widening of Sunset Highway. Project includes an encased, suspended crossing of Bronson Creek.

Est. Construction Cost: \$180,000
Est. Construction Date: March 2010

Other Projects

City of Washougal – New Ground Level Zone 4 Reservoir
City of Stevenson – White Cap Apartment Infrastructure